

YADAVINDRA PUBLIC SCHOOL PATIALA – 147001

TENDER NOTICE

Invites quotations by 17 May 2025
for the following:-

- (a) Waterproofing of boarding house roof with Dr Fixit. Approx area 15000 sqft.
- (b) Civil work in Junior School building for conversion of existing Dance room to Conference Hall and another room to Western Music room.
- (c) Supply of 120 Nos stackable PVC chairs Beige shade.
- (d) Supply & installation of 2 Ton 3 Star Split AC.

Detailed BOQ can be downloaded
from school website

www.ypspatiala.in

Size: w-4 x h-6 cm

YADAVINDRA PUBLIC SCHOOL, PATIALA			
WATERPROOFING - REMAINING AREA OF GBH ROOF			
Ser No	Nature of work	Unit	Area
(a)	Dr Fixit (URP 301) used for crack filling and repair work		
(b)	Dr Fixit Roofseal Classic - used for layer waterproofing in coating form after repair work	Sqft	14850
(i)	1st coat as primer with 1 ltr chemical + 0.5 ltr water.		
(ii)	2nd & 3rd coat as final finishing coat as perpendicular way		

}

YADAVINDRA PUBLIC SCHOOL, PATIALA

BOQ : CONVERSION OF JR SCHOOL DANCE ROOM TO CONFERENCE ROOM

Date

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Supply & fixing gypsum perforated tile 2' x 2' x 8mm over GI grid fastened with wire hangers to roof soffit at all heights. Make Gypco	Sqft	1550		
2	Supply & fixing PVC wall paneling over walls of approved shade and pattern . Make Décor	Sqft	1000		
3	Supply & applying 2 coats of OBD and enamel paint over already painted surface over walls and wooden surface. Make Asian	Sqft	3000		
4	Supply & fabrication of wooden stage made of 20mm thick plyboard 12' x 8' x 9" including vinyl floor and sides of approved shade	Sqft	140		
5	Supply & fabrication of wooden enclosure (height-10' & length 6' made of 20mm thick plyboard including internal painting	Sqft	120		
6	Supply & fixing curtain SS rod 20mm dia including hooks & lattoo	Nos			
	(i) 3'-6" Long	Nos	13		
	(ii) 5' -6" Long	Nos	2		
7	Electrical wiring: 1.0 mm copper insulated wire for fans and ceiling lights. Make - Havells	Job	1		
8	Electrical wiring and switch for AC (2 ton) with 2.5 mm copper wire	Job	1		
9	Supply & fixing LED lights 36 w 2' x 2' Make Havells	Nos	20		
10	Removal of ceiling fans and refixing with 2'-6" to 3' long hanging rod	Nos	12		
11	Supply & fixing 16 amp power plug & switches including wiring and PVC box. Make Havells	Nos	6		
12	Supply & fixing 5 amp switches & sockets including wiring and PVC box. Make Havells	Nos	10		
13	Supply & fixing 16mm sq 4 core Al-Insulated unarmoured cable	R/mtr	50		

YADAVINDRA PUBLIC SCHOOL, PATIALA

BOQ :CONVERSION OF ROOM NUMBER 23 TO WESTERN MUSIC ROOM IN JR SCHOOL

Date

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Supply & fixing HDF laminated floor tounge /grooved strips 4' x 6" x 10mm over existing hard surface of approved shade including edge fixing. Make Action TESA	Sqft	830		
2	Supply & fixing perforated gypsum 2' x 2' x 8mm tile for false ceiling over GI frame make GYPRO	Sqft	790		
3	Supply & fixing wall PVC panel over wall of approved shade. Make Décor	Sqft	280		
4	Supply & fixing perforated gypsum 2' x 2' x 8mm tile over 2' x 2' grid of 2" x 3/4 " partial wood frame including Anti termite treatment	Sqft	750		
5	Material and fabrication of wooden cabinets 2'x2'x2' of plyboard 19mm thick comprising shutters, fittings and internal painting and sunmica over shutters/ frosted glass 5mm thick.	Nos	48		
6	Supplying & applying OBD 2 coats over perforated board/tile of false ceiling and walls. Make Asian	Sqft	1650		
7	Supplying & applying enamel paint 2 coats over wood/steel surface. Make Asian	Sqft	260		
8	Repair to wooden stage made of 19mm thick plyboard 12' x 8' x 1' including PVC floor over top & sides (to be shifted from dance room).	Nos	1		
9	Supply & fixing ceiling fan hanging rod 2'-6" to 3' long including refixing of ceiling fans	Nos	6		
10	Supply & fixing LED ceiling light 2' x 2' x 36 W Make Heavells	Nos	8		
11	Electric wiring to ceiling lights and repair or replacing switch board and consealing existing	Job	1		
12	Supply & fix broken window panes 5mm thick. Make Atul	Sqft	10		
13	Supply & fixing glass putin to existing window panes where damaged in 7 windows	Job	1		

Total