

Published in the Jag Bani (Patiala Bani) on 04 Dec 2025.

TENDER NOTICE

**YADAVINDRA PUBLIC SCHOOL
PATIALA 147001**

Invites quotations by 10th Dec 2025 for repair to MS structure of Lighting Towers (height approx. 50'). Details can be downloaded from school website www.ypspatiala.in .

YADAVINDRA PUBLIC SCHOOL, PATIALA

BOQ : REPAIR TO TWO LIGHTING TOWERS INSTALLED IN THE STADIUM

Date

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Removal of rusted MS sheet and supporting MS pipes of repair way at height of 50' approx and stacking at appropriate place as instructed at site.	Sqft	340		
2	Supply, hoisting, cutting to required size and fixing of intermediate support MS pipe about 4' in length, dia 3" Heavy duty . To be welded with main structure member of repair bay at height 50' approx	Rft	104		
3	Supply, hoisting, cutting to required size and fixing of MS sheet 3mm thick. To be welded with main structure member of repair bay at height 50' approx	Sqft	340		
4	Painting one coat of epoxy primer and two coats of Aluminium Paint	Sqft	680		
	Total including GST			₹	0

Note

- 1 Repair work is to be carried out at approx 50' height
- 2 Rates coated shall include the cost of scaffolding /Hydra crane
- 3 Safety precaution measures to be strictly adhered to.
- 4 School authorities shall not be responsible for any kind of mishap
- 5 Electric supply shall be provided by the school.
- 6 Connecting lead for welding set /cutting machine shall be provided by the contractor and he must ensure that this wire is properly insulated.
- 7 Ensure that electric supply of lighting towers is cut off before mounting it for repair.

$\frac{1}{2}$