

Published in the Chandigarh Tribune on 10 Jan 2026.

TENDER NOTICE

**YADAVINDRA PUBLIC SCHOOL
PATIALA 147001**

1. Invites quotations by 25th Jan 2026 for :-
 - A) Providing & fixing Aluminium slats/Louvers over the external boundary wall of School.
 - B) Making platform for mounting Armoured Tank.
 - C) P/F Prefabricated store size 86' x 20' x 14'.
 - D) Demolition of existing store shed size 100' x 15'
 - E) Overhead water tank repairs
2. Solar Inverter 100 KWp by 12th Jan
3. Details can be downloaded from school website www.ypspatiala.in

YADAVINDRA PUBLIC SCHOOL, PATIALA
PROVIDING & FIXING ALUMINIUM SLOTS/LOUVERS OVER THE EXTERNAL
BOUNDARY WALL LENGTH 700 MTR (APPROX)

Ser No	Nature of work	Rate per sqft
1	Area to be covered 700m x 1.2m of boundary above existing brick work and to be fixed to existing MS grill with screw/nut-bolts/welding	
	Total including GST	

BOQ : PLATFORM FOR ESTABLISHING ARMoured TANK (THE VIJAYANTA)**Weight - 40 Ton**

Date

Ser No	Description of work	AU	Qty	Rate	Amount
1	Excavation in foundation	Cft	515		
2	PCC 1:4:8	Cft	160		
3	Brick work in CM 1:4	Cft	350		
4	Soil filling	Cft	540		
5	Filling of 40mm gravel	Cft	240		
6	Flooring PCC 1:2:4 , 50mm thick	Cft	95		
7	Polished Granite Jet Black 18-20mm thick including making gola	Sqft	326		
8	Decorative Stainless steel chain	Rft	100		
9	SS Vertical post for fixing chain 2½ " dia x 2' height with end cap	Nos	20		
10	Inauguration and Tank History Plate two numbers of size 2' x 2' each	Nos	2		
	Total including GST				

BOQ : REPAIR TO RCC OVERHEAD WATER TANK

Ser No	Description of work	Amount
1	Following works required to be carried out for repairs to overhead water tank:-	
A)	Repair to internal/external plaster in CM 1:3 of dome/storage tank	
B)	Repair to MS ladder	
C)	Snocem to complete structure	
D)	Painting to in/out water pipes	
E)	Water level indicator	
F)	Cleaning of storage tank	
G)	Applying Waterproofing compound internally	
	Total including GST	

YADAVINDRA PUBLIC SCHOOL, PATIALA
PROVIDING & FIXING PRE-FABRICATED STORE

Ser No	Nature of work	Amount
1	Providing and fixing pre-fabricated store size 86' x 20' x 14'-12' with door windows and PCC flooring 2"	
	Total including GST	

Note desired parties can visit the site for any clarification related to site conditions before quoting the rates

YADAVINDRA PUBLIC SCHOOL, PATIALA

DEMOLITION OF STORE SHED

Ser No	Nature of work	Amount
1	Demolition of existing store shed considting mainly following items of work	
a)	Removal of profile sheets roofing]
b)	Removal of MS trusses and purlins	
c)	Dismantling of brick walls 9" thick	-
d)	Removal of Steel doors/windows and ventilators	
e)	Removal of PCC flooring and plinth protection including sub base.]
	Total including GST	

Note

- 1 Desired parties to visit the site before quoting the rates.
- 2 Quote rates separately for :-
 - A) If material retrieved taken by the Vendor.
 - B) All material of roofing and steel door/windows is retained by the school and to be stacked at designated place.