

Published in the Jag Bani (Patiala Bani) on 12 May 2026.

TENDER NOTICE

YADAVINDRA PUBLIC SCHOOL PATIALA 147001

Invites quotations by 18 May 2026 in sealed envelope, duly addressed to Headmaster Yadavindra Public School Patiala for:-

- A) Renovation work of Media room.
- B) Construction of Gate, Grain Store, Saddle room & toilet.
- C) Demolition of existing shed & fabrication of profile Sheet Shed
- D) Covering of Amphitheatre.
- E) Boring of new tubewell 15 HP.
- F) Repair work to overhead RCC water tank.
- G) Provn & fixing cushion sheets & back of library chairs.
- H) Roof Water proofing with Dr Fixit.
- J) Repair & painting to Steel cupboards.
- K) Painting work to 10 quarters.
- L) Fabrication of canopy for drinking water area.
- M) Repair to servant quarters.

Visit www.ypspatiala.in for detailed specifications.

**BOQ FOR RENOVATION OF MEDIA ROOM AT
YADAVINDRA PUBLIC SCHOOL, PATIALA**

Size 35' x 17'-3"

(DATE : 07/05/2026)

Ser No	Nature of work	AU	Qty	Rate	Amount
1	Provision and laying vitrified double charged floor tiles 2' x 2' laid over 25 to 40mm thick CM 1:3 bed	Sqm	57		
2	Supply & fixing gypsum 2' x 2' tiles in false ceiling over GI frame with hangers . Make Gypco	Sqm	57		
3	Supply & fixing PVC wall paneling as per approved sample. Make :	Sqft	540		
4	Supply & fixing Aluminum partition section 4" x 1 ³ / ₄ " partly glazed and partly panelled including door shutter	Sqft	390		
5	Supply & fixing wooden chowkath double patam section 5" x 2 ¹ / ₂ " size 4' x 6'-6" of Red Mirandi including fixing	Nos	1		
6	Supply & fixing gauged door shutter of Red Mirandi 35mm thick 35mm thick including fittings	Nos	1		
7	Supply & fixing panel door shutter 40mm thick of Red Mirandi size 3'-6" x 6'-4" including necessary fittings	Nos	1		
8	Supply & fixing glass panes 4mm thick Make Saint Gobin	Sqft	18		
9	Material & labour for closing existing window with 12mm thick plyboard	Sqft	36		
10	Supply & fixing LED light 2' x 2', 36w Make Havels	Nos	9		
11	Supply & fixing ceiling fan 1200 mm with 3' long rod & electronic regulator. Make Havels including wiring	Nos	6		
12	Provision of AC electrical points including conduits and consealed wiring	Nos	3		
13	Supply & fixing 5 amp switches, wiring and PVC box of required size Make Havels	Nos	18		
14	Supply & fixing louvers for 8'x4' windows of approved quality	Nos	3		
15	Provision and applying 2 coats of OBD over putti filling one coat over walls and painting over wooden surface/MS grills	Sqft	1300		
16	Modification/repairs to existing wooden Stools as directed at site (size 2' x 1 1/2' x 1') including paint and sunmica	Nos	40		
	Total including GST				

BOQ : CONSTRUCTION OF GATE No 5

Date

Ser No	Description of work	AU	Qty	Rate	Amount
1	Excavation in foundation, returning & filling of soil	Cft	130		
2	PCC 1:4:8	Cft	16		
3	Brick work in CM 1:4	Cft	428		
4	Ornamental work in Brick work and plaster	LS	1		
5	Supply & fabrication of MS gate as per existing desizn including hold fast, pivots and steel ball and fixing in position. Drawing attached	Kg	600		
6	Providing and rendering cement plaster in CM1:3, 15mm thick	Sqft	288		
7	Supplying and applying exterier paint 2 coats over 1 coat of putty including water primer. Make Asian	Sqft	288		
8	Supplying and applying Al paint 2 coats over 1 coat of primer Make Asian	Sqft	180		
9	RCC in column 1:2:4, column size 1' x 1' x 14' with base 4' x 4' x 8"	Cft	50		
10	Supplying, fixing and cutting steel bars 12mm, 16mm and 8mm in column and column base	Kg	140		
11	Providing and fixing Gate lights as per existing design including its wiring and PVC conduit	Nos	2		
12	Repair to footpath and drain outside the Gate	LS	1		
	Total including GST				

BOQ : CONSTRUCTION OF GRAIN STORE, SADDLE ROOM & WASHROOM

Ser No	Description of work	AU	Qty	Date	
				Rate	Amount
1	Excavation in foundation, returning & filling of soil	Cft	600		
2	PCC 1:4:8, 4" THICK	Cft	100		
3	Brick work in CM 1:6	Cft	790		
4	Providing & fixing profile sheet .48mm thick in walls & roof	Sqft	2400		
5	Supplying & fixing MS frame structure of various sections as required to fix profile sheets in wall & roof using MD vertical 3" channel and as in roof members, purlins shall be of 2" x 1 1/2 " sq ms pipes.	Kg	1300		
6	Earth filling under floor	Cft	500		
7	Supply & laying PCC 1:4:8 4" thick under floors	Cft	170		
8	Supply & laying PCC flooring in panel using PVC strips 40mm floor thickness 2"	Sqft	515		
9	Supply & fixing MS door shutters 4' x 7' made of MS angle 40 x 40 x 5mm , 40mm x 5mm flat and profile sheet panels	Nos	2		
10	Supply & fixing MS door shutters 2½' x 7' made of MS angle 40 x 40 x 5mm , 40mm x 5mm flat and profile sheet panels for toilets	Nos	1		
11	Supply & fixing MS ventilator/window 2' x 3' made of MS angle 40 x 40 x 5mm , 40mm x 5mm flat including glazing & gauging	Nos	3		
12	Provision & rendering cement plaster in 1:5 CM, 15mm thick	Sqft	430		
13	Provision and applying 2 coats of painting over one coat of primer over MS frame of roof & wall members including door/window vents.	Job	1		
14	Supply & applying OBD 2 coats over plastic surface	Sqft	430		
15	Providing & fixing Indian type WC with cistern & PVC connection. Make Hindustan	Nos	1		
16	Providing and fixing 15mm CP bibcock	Nos	2		
17	Providing & fixing 15mm CP stop cock/ consealed	Nos	1		

18	Providing & laying anti skid 1' x 1' floor tiles of approved quality & shade	sqft	30		
19	Providing & fixing wall tiles 1' x 1½' glazed tiles	Sqft	105		
20	Providing & fixing light point including wiring & conduits	Nos	4		
21	providing & fixing UPVC pipe 20mm dia for water supply line	Rft	100		
22	Providing and fixing 4" dia PVC pipe for sewage connection including required bends etc	Rft	15		
	Total including GST				

BOQ : DISMANTLING OF EXISTING STORE AND CONSTRUCTION OF ESTATE STORE SHED

Ser No	Description of work	AU	Qty	Date	
				Rate	Amount
1	Dismantling of existing store shed 95' x 16' made of profile sheet roofing, MS tu=russes, BB work in CM walls, PCC flooring, Rolling shutter, MS bars rolling window.				
(a)	If the material retrieved taken by the vendor				
(b)	If the material retrieved is retained by school with bricks completely clean.				
2	Excavation in earth	Cft	1135		
2	PCC 1:4:8, 4" THICK	Cft	189		
3	Brick work in CM 1:6	Cft	800		
4	Providing & fixing profile sheet .48mm thick in walls	Sqft	1950		
5	Supplying & fixing MS frame structure of various sections as required to fix profile sheets in wall & roof using MD vertical 3" channel and as in roof members, purlins shall be of 2" x 1 1/2 " sq ms pipes.	Kg	1300		
6	Earth filling under floor	Cft	1900		
7	Supply & laying PCC 1:4:8 4" thick under floors	Cft	425		
8	Supply & laying PCC flooring in panel using PVC strips 40mm floor thickness 2"	Sqft	1300		
9	Fixing of door - 07 Nos & windows - 04 Nos, Ventilator - 01 including painting	Job	1		
10	Supply & fixing glass panes 5mm thick with putty to steel windows and ventilators	Sqft	110		
12	Provision & rendering cement plaster in 1:5 CM, 15mm thick	Sqft	1500		
13	Provision and applying 2 coats of painting over one coat of primer over MS frame of roof & wall members including door/window vents.	Job	1		
14	Supply & applying snocem 2 coats over plastered surface	Sqft	1500		
15	Providing & fixing Indian type WC with cistern & PVC connection. Make Hindustan	Nos	1		
16	Providing and fixing 15mm CP bibcock	Nos	2		

17	Providing & fixing 15mm CP stop cock/ consealed	Nos	1		
18	Providing & laying anti skid 1' x 1' floor tiles of approved quality & shade	sqft	30		
19	Providing & fixing wall tiles 1' x 1½' glazed tiles	Sqft	105		
20	Providing & fixing light point including wiring & conduits	Nos	4		
21	providing & fixing UPVC pipe 20mm dia for water supply line	Rft	100		
22	Providing and fixing 4" dia PVC pipe for sewage connection including required bends etc	Rft	100		
23	Provision & laying plinth proection in PCC 1:2:4 , 2" thick over 1:4:8, 4" thick & 2' wide	Sqft	400		
24	Fixing & hoisting roof truses 9 Nos and purlin 6 Nos retrieved from dismantling including painting	Job	1		
25	Fixing of profile sheets in roof, retrieved from dismantling incl ridges	Sqft	1900		
	Total including GST				