

BOQ FOR PROVIDING & LAYING VITRIFIED FLOOR TILES IN JUNIOR WING

Sr No.	Description of item of work	Unit	Area/Qty	Rate	Amount
1	Chipping, scraping and cleaning of existing terrazzo flooring surface including removal of loose material, dust and debris complete for preparation of surface before laying of tiles.	Sqft	15000		
2	Providing and laying full body charged vitrified matt finish floor tiles of size 2' x 2' of approved make, shade and design over 20 – 30mm thick cement mortar bed in CM 1:3, including proper leveling, alignment, cutting wherever required and filling of joints with epoxy grout of approved color/ shade complete in all respects. Make : Orient Bell (Sahara Golden)	Sqft	15000		
3	Removing flush doors from existing MS frames, cutting to required size and refixing in position due to increase in floor level, including replacement of if any hinges, screws or fittings during dismantling and refixing complete.	No.	30		
4	Removal and disposal of malba/debris generated during execution of work and cleaning of site after work complete.	L/S			
			Total including GST		