

YADAVINDRA PUBLIC SCHOOL, PATIALA

M/s Raashi Advertising,
Old Bishan Nagar,
Patiala.

Dear Sir,

Please publish the following advertisement in Jagbani (Patiala Bani) on dated 8th June, 2026.


Bursar

Headmaster

TENDER NOTICE

**YADAVINDRA PUBLIC SCHOOL,
PATIALA**

Invites quotations by 15th June, 2026 from contractor for work of repair and water proofing of RCC overhead water tank including internal and external surface treatment, MS railing and RCC stair / Chajja. Download details/specification from school website www.ypspatiala.in. Drop sealed quotation at school Office

BOQ – Repair of RCC Over Head Water Tank

Name of Work: Repair and Waterproofing of RCC Over Head Water Tank including internal/external surface treatment, repair of MS ladder/railing and external Snowcem finish.

Tank Capacity: Approx. 1.0 Lac Litres

Height: Approx. 50'-60'

Sr. No.	Description of Item	Unit	Qty.	Rate	Amount	Remarks
1	Scraping/removal of loose plaster, damaged concrete and cleaning of complete internal surface of RCC water tank including disposal of debris.	Sqft	1600			Internal surface preparation
2	Providing and applying one coat of waterproofing chemical/Dr. Fixit treatment on complete internal surface of tank.	Sqft	1200			Waterproof base coat
3	Providing 12-15 mm thick cement plaster in CM 1:3 over treated internal surface including curing complete.	Sqft	1600			Internal replastering
4	Injection grouting in RCC cracks/leakage portions wherever required to stop seepage/leakage complete.	Job	1 Job			Leakage treatment
5	Repair/replacement of damaged RCC portions, honeycombing and chajjas wherever required including polymer mortar treatment & required shuttering	Cft	110			Structural repair
6	Repair of existing MS ladder, MS railing and access steps from ground level to top of tank including welding, grinding, straightening and replacement of damaged portions wherever required.	Rft	90			MS fabrication repair

Sr. No.	Description of Item	Unit	Qty.	Rate	Amount	Remarks
7	Applying one coat of red oxide primer and two coats of synthetic enamel paint on MS ladder, railing and steps complete.	Sqft	180			Painting of MS work
8	External surface cleaning/scraping of tank including removal of loose paint/plaster and redone of plaster	Sqft	1200			External preparation
9	Providing and applying waterproof exterior grade Snowcem finish/two coats on complete external surface of overhead water tank.	Sqft	2200			External finishing
10	Scaffolding/bamboo staging, labour, curing, tools & plants and all incidental works complete for execution of above items. Height 50 to 60 ft	Job	1 Job			Complete work

Notes:

- All materials shall be of approved make and quality.
- Contractor shall ensure proper safety arrangements during work at height.
- Water tank shall be cleaned properly before handing over.
- Rate shall include labour, material, transportation, curing, scaffolding and all taxes.
- Measurement shall be taken at site as per actual executed quantities.