

YADAVINDRA PUBLIC SCHOOL, PATIALA

Subject: Tender Notice / Call for Quotation for Provision of Cricket Practice Net Facility at School Premises

Sealed quotations are hereby invited from reputed and experienced contractors/firms for the following works at **Yadavindra Public School, Patiala**.

Interested contractors/firms are requested to submit their item-wise rates against the following BOQ:

S. No.	Particular of item	Approx. Qty	Rate (Rs)	Amount (Rs.)
1	Structural steel work consisting of M.S. pipes 50 mm (2II) outer dia and 2 mm thick, 40 mm outer dia 2 mm thick, M.S. wire 4.00 mm dia, M.S. flat 100 mm wide 6mm thick, M.S. disc 50 mm dia 6mm thick duly welded, supply fabricated and erected at site of work. I. M.S. Pipes 50 mm outer dia 2.0 mm thick. = 672.00 Kg. II. M.S. Pipes 40 mm outer dia 2.0 mm thick. III. M.S. wire 4.00 mm dia = 3.91 Kg IV. M.S. flat 100 mm wide 6.0 mm thick = 56.52 Kg V. M.S. disc 50 mm dia 6.0 thick = 3.88 Kg Total = 736.31 Kg	736.31 Kg		
2	Earth Work in excavation in foundation, trenches etc. in all kind of soil as per design and darning.	921.00 C.ft		
3	Excavation in surface dressing not exceeding 30.0 cm in depth.	585.00 Sq.ft		
4	Providing and laying cement concrete 1:5:10 with 40.00 mm gauge stone ballast.	242.55 C.ft		
5	Providing and laying cement concrete 1:2:4	96.6 C.ft		
6	Painting new steel surface with two coats of metallic paint and one coat with red oxide primer	882.45 Sq.ft		

7	First class brick work laid in C.M. 1:5 in foundation and plinth	226.41 C.ft		
8	Providing and laying brick edging in full brick width and half brick depth	105 R.ft		
9	Providing and laying cement concrete 1:2:4, 40mm thick mixed with chemical hardener.	966 Sq.ft		
10	Cement sand plaster 20.0 mm thick in C.M. 1:5	501.75 Sq.ft		
11	Providing and fixing cricket pitch net of 3.00 mm thick nylon thread as per specification	11,125.00 Sq.ft		
12	Providing and fixing AstroTurf on the existing cricket pitch as per specification.	650 Sq.ft		
13	Providing and laying glass strips 40.00 mm wide and 4.0 mm thick in joints of cement concrete flooring	519 R.ft		
14	Centring and shuttering as per specification	681.60 Sq.ft		
15	Dismantling cement concrete 1:3:6 or richer	108.00 C.ft		
16	Welding M.S. pipe at the ht. of 17.0'(labour only)	411.00 kg		

Terms & Conditions

1. Contractors/firms shall quote their **item-wise rates** against the above BOQ.
2. The quoted rates should clearly mention **GST and other applicable taxes/charges**.
3. The contractor shall inspect the site before submitting the quotation.
4. The quantities mentioned above are approximate and payment shall be made as per actual work executed and measured.
5. The work shall be carried out as per the specifications and instructions of the School Authority.
6. The contractor shall be responsible for the quality of material and workmanship.

7. The contractor shall ensure proper safety arrangements during execution of the work, particularly for work at height.
8. Any damage caused to school property during execution shall be repaired/made good by the contractor at his own cost.
9. The School Authority reserves the right to accept or reject any or all quotations without assigning any reason.
10. The successful contractor shall complete the work within the time period specified by the School Authority.

Submission Details

Last Date for Submission of Quotation: 12 October, 2026

Venue: Board Room, Yadavindra Public School, Patiala

Quotations should be submitted in a **sealed envelope** clearly mentioning:

“QUOTATION FOR CIVIL, STRUCTURAL & CRICKET PITCH WORKS”

PLAN OF CRICKET PITCH

