“Published in `The Jagbani (Patiala Bani) on 23 Oct 2026”

TENDER NOTICE

YADAVINDRA PUBLIC SCHOOL
PATIALA 147001

Invites quotations for the following works:-

(a) Laying Precast Chequered tiles 20mm thick in Junior School, area approx. 4000 sqft.

(b) Repairs to residence of Matron, Girls Boarding House

Drop sealed envelope by 30 Oct 2026 in the Quotation Box placed at School Office. Visit www.ypspatiala.in for detailed BOQ.

YADAVINDRA PUBLIC SCHOOL, PATIALA

BOQ : REPAIRS TO GBH MATRON'S RESIDENCE

Ser No	Description of item	AU	Qty	Rate	Amount
1	Removal of old cement plaster from soffit of roof slabs including disposal of malba from 2nd floor to deisgnated place in the campus	Sqft	650		
2	Provision and laying epoxy bond (adhesive) coat before laying shot concrete	Sqft	650		
3	Supply & fix ISMB 150 including welding to MS plates 150x150x6mm / embeded in walls with Cement concrete 1:2:4	Kg	250		
4	Supply & fix SHS 40x40x2.6mm welded to above RHS to secure welded mesh	Kg	600		
5	Supply and fix welded mesh size 50mm x 50mm x 5mm with the steel frame work	Kg	450		
6	Provision and laying shot concrete 1:1 1/2 : 3 with 10mm stone aggregate thickness 40 - 50mm	Cft	90		
7	Supply & laying cement plaster 6mm thick in CM 1:3 over the shot concrete	Sqft	650		
8	Supply & applying 2 coats of OBD/enamel paint over walls, soffit and metal/wooden members including one coat of primer	Sqft	2000		
9	Removal and refixing of ceiling fan & tube lights where required including connection	LS	1		
	Total Amount (including GST)				

Signatures of the contractor with stamp

YADAVINDRA PUBLIC SCHOOL, PATIALA

BOQ : LAYING CHEQUERED FLOOR TILES IN JUNIOR SCHOOL

Sr. No.	Description of Item	Unit	Qty.	Rate	Amount
1	Supplying and laying precast chequered tiles 20mm thick in ordinary grey cement without chips laid on 20mm thick bed of CM 1:3 with neat cement slurry between joints over the existing floor including cleaning and scrapping of dust etc	Sqft	4000		
	Total (including GST)				